



July 25, 2024

QUOTATION

Merced County Regional Waste Management
7040 N Hwy. CA 59
Merced CA 95348
Email: slagterc@cityofmerced.org

PORTABLE CENTURION DIGITAL

FULLY SELF-CONTAINED PORTABLE TRUCK SCALE 70' x 11'
100K CLC
3/8" TREAD DECK

CPD-M 77K STAINLESS DIGITAL CELLS DD700 DESKTOP INDICATOR

\$76,720.00

SIGHT RAIL, SINGLE PIPE, 8" HEIGHT, SAFETY YELLOW

\$4,410.00

PORTABLE RAMP 20 X 11

STEEL RAMP DESIGNED TO BE USED IN CONJUNCTION WITH HYBRID OR
CENTURION PORTABLE TRUCK SCALE
RAMP SETS AGAINST PORTABILITY FRAME END BULKHEAD

\$21,000.00

Load cells come with lifetime warranty if LSI performs Pm service 3x a year

TMU 295 printer

\$ 595

Install by LSI Scales

\$ 9,995

Crane estimate

\$ 2,500

Freight

\$ 7,000



Sales Tax (Parts Only) \$102,725 @8.25

\$ 8,474.81

For installation of this project LSI will need a level foundation for scale, along with conduit running from scale house to scale and 110 power source in scale house. LSI can have your scale installed and functioning the same day as delivery. This scale can be moved if in the future you decide on a new location.

Please call me with any questions. Thank you for this opportunity as we value your business.

Thank you

Frank Lasick
Kim Lasick
LSI SCALES
Town & Country Scales
Phoenix Scales
Cell 559/540-4887
www.Michael@lsiscales.com

Quote valid for 14 days from above date

Exclusions: All 115 VAC power and utility requirements to perform work.

All necessary building permits, certified drawings, inspections, and Weights & Measures fees. Additional peripherals: Computers, software, traffic lights, remote displays, weight tickets, intercoms, cameras, printers etc. Removal or repair of unidentified obstructions. Scale house, post, wall, or enclosure for instrumentation Delays caused by an Act of God, abuse, theft, or improper shipping and handling. Any grading required around scale foundation work. Pit and electrical work done by others.