



**QUOTATION
NO. 11286 R**

**CITY OF MERCED
678 W 18TH ST
MERCED, CA 95340-4700
SOURCEWELL MEMBER ID # 2325**

DATE: 7/18/2022
TERMS: NET 30
F.O.B: FRESNO
MFG PRODUCT: SEE BELOW
INSTALL: SEE BELOW

QTY	PART NO.	DESCRIPTION	PRICE	EXTENSION
PB LOADER CONTRACT NO. 080521-PBL SOURCEWELL CONTRACT - DISCOUNTED PRICES				
DUMP BODY & ACCESSORIES				
1	PBLDB-10	PB LOADER SUPPORT BODY, 15 FT 12-14 YARD, HPT53-130 CLASS 80 NTEA HOIST, 3/16" STEEL FLOOR AND TAILGATE, 10 GAUGE STEEL BALANCE, 38" SIDES, 54" FRONT AND 46" REAR, 12" SPREADER APRON, 1/4 CABSHIELD, LED LIGHTS, WIRING HARNESS & BACKUP ALARM, PUMP, CONTROLS, TANK, VALVE, MUD FLAPS, STEEL MUDGUARDS, HOT SHIFT PTO, AIR TAILGATE, PAINT BLACK, INSTALLATION		\$40,773.00
1	2014-00	SIDE BOARDS WOOD W/ LINSEED OIL		\$832.00
1	50502-00	PULL TARP MANUAL - VINYL FOR ASPHALT W/ ROPE HOOKS		\$2,867.00
1	393-00	PULL LADDER EZ-STEP		\$712.00
2	2001-10	STAINLESS-STEEL SPRING ASPHALT LUTE HOLDER	\$149.00	\$298.00
1	7000-24	TOOL BOX 24"		\$929.00
LIGHTS & SAFETY EQUIPMENT				
1	7220-00	PRECO 220 BACKUP ALARM		\$176.00
MARKET PRICE ITEMS				
1		UPGRADE ABOVE BODY TO INCLUDE 1/4" AR400 FLOOR, SIDES, REAR, AND FRONT, ONE (1) HORIZONTAL SIDE BRACE, 1/2 CAB SHIELD, HOOKS FOR MUD FLAPS, GLAD HANDS, HITCH PLATE W/ D-RINGS AND 7-WIRE PLUG, 45-TON PINTLE (PREMIER 270A), TWO (2) WHELEN MODEL L31HAF STROBE W/ BRANCH GUARD, TWO (2) WHELEN MICRONS, PULL-DOWN STYLE DITCH GATE CENTER OF TAILGATE		\$12,614.00
MARKET PRICE CHASSIS				
1		NEW 2023 FREIGHTLINER M2 106 SET BACK AXLE CONVENTIONAL CHASSIS COMPLETE WITH CUMMINS L9 330HP @ 2200 RPM DIESEL ENGINE, ALLISON 3500 RDS AUTOMATIC TRANSMISSION WITH PTO PROVISION, DASH MOUNTED PTO SWITCH, FOUR (4) SETS OF KEYS, 5 LB. FIRE EXTINGUISHER, 80 GAL. ALUMINUM FUEL TANK, TANDEM REAR AXLE WITH HENDRICKSON HAULMAAX @40,000# REAR SUSPENSION, 18,000# TAPERLEAF FRONT SUSPENSION, MAXION STEEL DISC WHEELS, CAB PAINTED WHITE		\$115,077.00
TOTAL:				\$174,278.00
FREIGHT:				\$1,200.00
TOTAL WITH FREIGHT:				\$175,478.00
NOTES: 1.LEAD TIME FOR BODY PRODUCTION IS 120 DAYS, WITH AN ADDITIONAL 120-150 DAYS TO INSTALL AFTER RECIEPT OF CHASSIS AND BODY. 2. LEAD TIME SUBJECT TO CHANGE AT TIME OF ORDER 3. QUOTE IS VALID FOR 90 DAYS. Delivery times are approximate.				