


PROPOSED OFF-SITE PUBLIC INFRASTRUCTURE IMPROVEMENTS Childs & B Street Affordable Housing Project



Proposed Off-Site Public Infrastructure Improvements for Childs Court Apartments

New and replaced sidewalks:

- East side of B Street from E. Childs Avenue to E. 15th Street (approx. 2,225 linear feet)
- West side of B Street from E. Childs Avenue to E. 15th Street (approx. 2000 linear feet)
- E. Childs Avenue along project frontage (approx. 327 linear feet)
- North side of E. 13th Street from corner of E. 13th/B Street in front of former Juvenile Hall (approx. 150 linear feet)
- North side of E. 15th Street to complete missing sidewalk connection in front of the Merced Monuments establishment (approx. 150 linear feet)

ADA curb ramping at the following corners:

- North and South corners of E. 13th Street at B Street
- North and South corners of abandoned E. 14th Street at B Street (former Juvenile Hall and rear of Marie Green Psychiatric Center)
- East and West corners of E. Childs Ave and B Streets at "T" intersection
- East and West corners of E. 15th Street and the northern section of B Street at Merced Monuments establishment

New Pedestrian Crosswalks:

- Across B Street at Childs Avenue
- Across the northern section of B Street at E. 15th Street
- Across former E. 14th Street at B Street (former Juvenile Hall and rear of Marie Green Psychiatric Center)
- Across E. 13th Street at B Street
- Across B Street at E. 13th Street corner ramp

New Class II Bicycle Lanes:

- East and Westbound sides of E. 15th Street from G Street to B Street (approx. 0.44 miles each direction)
- East and Westbound sides of E. 13th Street from G Street to B Street (approx. 0.44 miles each direction)
- North and Southbound sides of B Street from E. 15th Street to E. Childs Avenue (approx. 0.42 miles each direction)
- Complete connection to existing Westbound bicycle lane on E. Childs from B Street along project frontage

New Class III Shared-Lane Markings ("Sharrows"):

- North and Southbound directions of D Street between E. 13th Street and E. Childs Avenue (approx. 0.33 miles each direction)
- North and Southbound directions of E Street between E. 13th Street and E. 11th Street (approx. 0.13 miles each direction)

Full "Complete Streets" Street improvements along east and west sides of B Street:

- New curbs, gutters, and storm drains
- New streetlights
- New street trees

Storm Basin/Public Park – approx. one-acre storm drain basin to collect storm water runoff from E. 15th, E. 13th, and B Streets) during rain season; public park in dry season:

- All-weather play structures
- Lawn and landscaping
- Lighting
- Benches

New Transit Bus Pullout in front of project site on B Street:

- New transit bus pullout (one bus-width long)
- New multi-modal bus shelter, to include bench with all-weather shade structure, bicycle racks, refuse receptacles, and bicycle maintenance kiosk)